



# हिमाचल प्रदेश केन्द्रीय विश्वविद्यालय Central University of Himachal Pradesh

धर्मशाला, जिला - कांगड़ा, हिमाचल प्रदेश - 176215  
Dharamshala, District Kangra (HP)-176215

Ref. No: 01/2023-24/CUHP/ENGG/NIQ

Dated: 12.05.2023

## **NOTICE INVITING QUOTATION**

For and on behalf of Central University of Himachal Pradesh, sealed Quotations are hereby invited by the undersigned for “**Aluminium partition work for setting up Cell Culture Lab in Dept. of Animal Science (Room 114) and Research Lab in the Dept. of Physics & Astronomical Sciences at Shahpur parisar**” from contractors/firms enlisted/ empaneled with Central/ State Govt. Organization/ Central Autonomous body/ Central Public Sector Undertaking as per schedule attached at **Annexure-II**. The sealed envelope containing quotation shall be superscribed with the **Name of Work, Quotation Enquiry Ref. No. & Date** and shall reach the O/o Executive Engineer, Administrative Block, CUHP, Dharamshala by registered post or delivered personally latest by **19.05.2023 up to 11:00 AM** and shall be opened on the same day at **11:30 AM** in the O/o Executive Engineer, Administrative Block, CUHP, Dharamshala in the presence of intending bidders/contractors or their authorized representatives.

Application for Quotation Document must be accompanied with the self-attested copies of the following qualifying documents:

- 1.) GST certificate.
- 2.) PAN Card.
- 3.) Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking.
- 4.) Signed copy of terms & conditions (Annexure-I)
- 5.) Schedule of quantities (Annexure-II)

**The approximate cost of the work is Rs. 2,31,526/- (Rupees Two Lacs Thirty One Thousand Five Hundred Twenty Six only).**

Detailed quotation document can be downloaded from the University website ([www.cuhimachal.ac.in](http://www.cuhimachal.ac.in) or [www.hpcu.ac.in](http://www.hpcu.ac.in)).

-sd-

**Executive Engineer**  
Central University of Himachal Pradesh  
Dharamshala, Distt Kangra. Himachal Pradesh

Copy to:

1. Notice board.
2. University Website.

-sd-

**Executive Engineer**

**Terms & Conditions**

1. The work is to be completed within **15 days**, to be reckoned from the next day from date of award of work.
2. The quantities of work in the schedule (refer **Annexure- 'II'**) are provisional and likely to vary (increase or decrease).
3. The prices quoted should be net inclusive of CP&OH charges, freight, Labour, T&P, Cartage, Lead/Lift and GST and nothing extra is to be paid.
4. Bidders are advised to visit the site before quoting the rates to assess the quantum and scope of work.
5. Payment shall be made only after the work is completed as per actual quantity and quantum of work executed satisfactorily; no advance shall be paid.
6. All material to be used on the work will have to be got approved from the Engineer-in-charge.
7. Compensation of delay of work will be @ 0.5% per day.
8. The quotation for the work shall have validity for a period of 30 days from the date of opening of quotations.
9. The contractor/firm has to abide by labour rules and regulations.
10. All applicable Taxes and Statutory Deductions shall be deducted from the final bill.
11. In case of any dispute, the decision of Vice-Chancellor, CUHP is final and binding on the contractor.
12. The Central University of Himachal Pradesh reserves the right to accept or reject any or whole quotation without assigning any reason thereof.
13. The firm/contractor shall be responsible for faithful compliance of the terms and conditions enunciated in this document. In the event of any breach of any of the terms and conditions, the assigned work may be terminated and further the work order may be got executed from another agency at risk and cost of the firm/Contractor.
14. In case of any queries/doubts the bidder(s) can visit the Office of Executive Engineer, CUHP at Dharamshala.

-sd-

**Executive Engineer**  
Central University of Himachal Pradesh  
Dharamshala, Distt. Kangra, H.P.

I acknowledge that I have read, and do hereby accept the terms and conditions contained in this quotation document.

Signature with date of bidder

Name (CAPITAL): \_\_\_\_\_

Address:

Contact no:

**BILL OF QUANTITIES**

<b>Name of Work: Aluminium partition work for setting up Cell Culture Lab in Dept. of Animal Science (Room 114) and Research Lab in the Dept. of Physics &amp; Astronomical Sciences at Shahpur parisar.</b>					
<b>Name of Bidder:</b>					
<b>S. No.</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately). For fixed portion: Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	kg	161.32		
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately). For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately): Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	kg	46.30		
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	sqm	22.42		
4	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge : Pre-laminated particle board with decorative lamination on both sides (Matte finish)	sqm	37.63		

5	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	no	3.00		
6	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150x10 mm	no	5.00		
7	Providing and fixing aluminium handles 125 mm, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete.	no	10.00		
8	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete: 250x16 mm.	no	4.00		
9	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete: Twin rubber stopper.	no	5.00		
10	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	sqm	18.00		
11	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 metres lead : Thickness above 10 mm up to 25 mm	sqm	1.65		
12	Dismantling and refitting of Godrej make six body optimizer including shifting from ground floor to second floor. The work has to be executed through authorized Godrej dealer/personnel's only.	job	1.00		
13	Removing existing aluminium partitions/doors including glass/panelling and stacking the same upto 50 m lead complete as per site requirement and directions of engineer-in-charge.	sqm	22.25		
14	Fixing of existing aluminium partitions/doors including cutting of existing aluminium sections/glass/panelling complete as per site requirements and directions of engineer-in-charge (Cost of EPDM rubber / neoprene gasket, CP brass screws is included in the item).	sqm	22.25		
				<b>Total (in Rs.)</b>	
	<b>Total Amount in Words:</b>				

-sd-

**Executive Engineer**

Central University of Himachal Pradesh  
Dharamshala, Distt. Kangra, H.P.

**Signature of bidder**

**Name:** \_\_\_\_\_

**Address:** \_\_\_\_\_